## **CREATING THE NEW TIDAL AREA, KREETSAND**

## WORKING WITH NATURE IN HAMBURG

### **IAPH Sustainability Awards 2023**

Jörn Gutbrod, Strategy and Innovation, Waterside Infrastructure, Hamburg Port Authority

26 May 2023

Agenda





Background: The Tidal Elbe Concept

Implementation: Creating tidal volume



Literally: Working with nature

Take a tour!

# **The Tidal Elbe Concept**



New tidal area Spadenlander Busch / Kreetsand



### **Estuaries**



are changing...



...and are changed







### Land reclamation and dykes





Herausgeber: Vermessungs- und Kartenstelle bei der Wasser- und Schifffahrtsdirektion Nord; Stand: 6/2006

### **Tidal range and measures**





## **Tidal pumping**







### Motivation: Increased need for dredging





### Fixing the estuary: The Tidal Elbe Concept





### 2006

# **Creating tidal volume**



New tidal area Spadenlander Busch / Kreetsand

## Creating tidal volume: pilot project Kreetsand







### **Pilot project Kreetsand**





- former spoil area / dewatering field, dyke foreland (tidal meadow landscape)
- planning area ca. 47 hectares
- dyke realigned in 1999
- mean altitude approx. +5.50 m above sea level







### **Range of layouts and modelling**

 Vorauswahl von 8 Varianten im Hinblick auf die zu erwartenden Unterschiede bei der Strömungs- und Sedimentationsmodellierung E1, E2, E3, E5, E6, Z1, Z3, M3



- 7. "Überschlägliche" Modellierung der vorausgewählten Varianten, Ergebnisdiskussion
- 8. Verbal-argumentative bzw. rechnerische Bewertung der Varianten anhand der Kriterien gemäß Punkt 5

#### 9. Auswahl von 3 Vorzugsvarlanten











## Planning process: criteria rating matrix



- Rating of the options using different criteria
- Creation of valuation units
  - target achievement
  - impact on subjects of protection
  - time line
  - costs
- To prioritize key criteria, the scoring assigns additional weight to:
  - Tidal hub attenuation
  - Sustainability of tidal low water
  - Restriction of sedimentation impacts
  - Preservation of alluvial forests and biotopes
- Sensitivity analysis to verify the results

Bewertung d	tung der Planungsvarianten V1 bis V3				Wichtunger åndern
			Tides starticl / These	Tendenz	100
		P1	l idepotential / Flutraum	auf	10
Zielerreichung:		<u> </u>	positiv: Maximierung des Tidepotentials		
		P2	positiv: möglichst starke Zerstreuung der Tideenemie	auf	5
Tidepotential			Nachhaltigkeit: Beschränkung Sedimentationsprozess	-	
Verringerung von		P3	positiv: Minimierung von Sedimentation / Unterhaltung	aD	12
Tideenergie Nachhaltigkeit			Dāmpfung	auf	17
		P4	positiv: Hoher Dämpfungseffekt bezogen auf die Tide im		
			Elbstrom		
			Cobutzeut Monooh		44
		N1	ositiv:	-	
			Erlebbarkeit durch visuelle Wahrnehmbarkeit	auf	8
			Erlebbarkeit durch Erreichbarkeit		
		N2a	Schutzgut Boden (Aushub unnatürlich)	auf	3
			positiv:		
			Rückbau belasteter Böden		
			Rückbau standortuntypischer Böden		
		N2b	Schutzgut Boden (Ausnub gewachsen)	ab	2
			Verbleib dewachsener Böden		
			Schutzaut Wasser	auf	5
			positiv:		
		N3	Gute Wassergualität		
			Großes Wasservolumen		
			Tide-Vielfalt		
			Schutzgut Pflanzen	auf	2
		N4a	positiv:		
			Vegetationstlachen insgesamt		
		Nab	ositiv:	auf	1
	Schutzgut Natur	1110	Schaffung zusätzlicher Auwald	- Contraction of the contraction	
Auswirkungen: Natur und Umwelt		N4c N5a	Schutzgut Pflanzen	ab	2
			positiv:		
			Minimierung entfernter Auwald		
			Schutzgut Tiere, Bedeutsame aquatische Lebensräume		5
			positiv:	aur	
	, F	Schutzgut Tiere Bedeutsame terrestrische Lebensräume			
		N5b	positiv:	auf	1
	N5		Schaffung zusätzlicher Auwald		
		N5c	Schutzgut Tiere, Bedeutsame terrestrische Lebensraume	ab	2
			positiv:		
			Minimierung entfernter Auwald		
		N6	Schutzgut Klima	auf	
			positiv: Augulaishafugitian		0
			Kaltluftentstehung		
			Maximierung Dauereinstauflächen		
		N7a	Schutzgut Luft		
			positiv:	ab	2
			Minimierung Ausbau- und Transportvolumina		
		N7b N9	Schutzgut Luft	auf	3
			positiv: Cohētrashalt, cohoffunz		
			Schutzaut Kultur und Sachaüter		
			positiv: Erhaltung	auf	0
	1		Province and		36
Tomaina		Te	Dauer bauliche Umsetzung	ab	
le mine			positiv: Minimierung der Bauzeit	ab	5
			······································		5
		K1	Investkosten	ab	10
Kosten			positiv: Minimierung Investkosten		10
		K2	Betriebskosten	ab	5
		. ·	positiv : Minimierung Betnebskösten		

### Planning process: detailed planning of the selected option









# **Working with nature**



New tidal area Spadenlander Busch / Kreetsand

### Winner of the PIANC Working with nature award (2014)







### Did we understand the environment?



- A 3D hydro-numeric model has been developed, tested, and can be utilized to closely examine the system.
- An ecological framework concept for the Elbe estuary has been established and agreed upon authorities, stakeholders, and the EU.

 $\rightarrow$  YES!





### Did we involve stakeholders and partners?



- Involvement of stakeholders from the early stages has been the cornerstone of the communication strategy.
- Local citizens, NGO's, relevant authorities were periodically and personally addressed to contribute to the development of the project.
- Engaging the wider public has been a pivotal aspect, both historically and in the future trajectory of the project. Notably, the project has been integrated into the International Building Exhibition (IBA 2013), fostering numerous excursions tailored towards students and schools. Furthermore, an innovative permanent information booth has been established to deliver valuable insights.



### Did we identify "win-win" solutions?



- The project goes beyond legal requirements, creating valuable estuarine habitat. It aligns with the Natura 2000
  management plan for the Elbe estuary and will contribute to a larger nature protection site. The new tidal area will
  particularly benefit fish species and the endemic Oenanthe conioides.
- The project increases knowledge (it is the first of its kind!) and awareness on tidal systems, sediment management and estuarine habitats.
- The site will be an attractive location for nature observation and recreation.



# Did we enable nature to play a significant role in the design process?



- The project aims to establish an initial state and subsequently allows natural processes to shape the site.
- The project is strategically designed to leverage the assistance of nature in sediment management.
- However, periodic maintenance work, such as water injection, will be essential to remove excessive sediments from the site.



# Did we adhere to the planning principles of Working with Nature, and was it effective in achieving our goals?



- The project was carefully planned from the beginning, involving an integrated process:
  - The project's objectives were established through extensive discussions with authorities, stakeholders, and the public.
  - A comprehensive understanding of the environment and its functioning was gained well before the project commenced, considering the estuary as a unified system.
  - The site selection process involved evaluating various options, considering multiple factors in a balanced manner.
  - The initial project design was chosen from a diverse range of possibilities.
  - Importantly, the project obtained legal approval without significant objections or delays





### **Dike Shed: An Information and Viewing Point**



- Information about the construction phase Kreetsand
- Information-center for the tidal Elbe concept
- Point of reference for IBA 2013
- Project within the EU-Project "TIDE"
- Costs: about 100.000 EUR; EU-funding rate: 15 %

## Take a tour



New tidal area Spadenlander Busch / Kreetsand

### **Change the landscape**



### Create 30 hectares of shallow water

- Remove deposited soils: ~ 1.2 million m<sup>3</sup>
- Remove natural ground: ~ 0.8 million m<sup>3</sup>
- Sum of excavation material: ~ 2,0 million m<sup>3</sup>
  - Soil for utilization: ~ 0.8 million m<sup>3</sup>
  - Soil for disposal: ~ 1.2 million m<sup>3</sup>



### Interventions in tidal floodplain forest







### Compensation for tidal floodplain forest





### Soil excavation





### Soil management





### How it happened – Nov. 2013





### How it happened – Aug. 2014





### How it happened – Aug. 2015





## How it happened – June 2016





### How it happened – July 2017





### How it happened – April 2018





### How it happened – May 2020





### How it happened – May 2021





### How it happened – Feb. 2022





#### New tidal area Spadenlander Busch / Kreetsand

### How it happened – May 2022







## Hamburg Port Authority AöR

Neuer Wandrahm 4 20457 Hamburg Joern.Gutbrod@hpa.hamburg.de Tel.: +49 40 42847-3057